



Liddell Power Station Stack Falls (Blast Event)

AGL MACQUARIE

Unique Attributes

- Close coordination between delivery, inhouse and third party engineering and specialist blasting teams
- Detailed methodology development, structural and blast engineering coordination, pre-weaken and drilling works, explosive charge installation, exclusion zone implementation, and environmental monitoring controls
- Practical staging of preparatory works to allow progressive verification of readiness prior to explosive loading and final event sign-off

Key Challenges

- Carefully sequenced felling methodology tailored to site constraints, adjacent assets and broader demolition staging requirements
- Execution within a live brownfield industrial environment with retained infrastructure, controlled access, strict exclusion zones, and multi-stakeholder oversight
- Extensive local community engagement, including live stream of blast event and dedicated media viewing zone

Project Statistics

169M | 7,500T
REINFORCED CONCRETE STACKS

>520KG
HIGH EXPLOSIVES

>140,000
TOTAL WORK HOURS

>4,400T
FERROUS & NON FERROUS SCRAP STEEL

- ENGINEERED MODELLING & 3D SIMULATION
- THIRD PARTY ENGINEERING
- TEMP WORKS ENGINEERING
- LIVE ENVIRONMENTS
- PUBLIC & ASSET PROTECTION
- STAKEHOLDER ENGAGEMENT
- HAZMAT REMOVAL
- ENVIRO CONTROLS & MONITORING
- MANUAL DEMOLITION
- MECHANICAL DEMOLITION
- SCAFFOLD
- LONG REACH DEMOLITION
- CUT & LIFT DEMOLITION
- CRANAGE & RIGGING
- PROPPING & BRACING
- EXPLOSIVE DEMOLITION
- WASTE TRANSFER
- CONCRETE RECYCLING
- STEEL RECYCLING
- MATERIALS SOLUTION MANAGEMENT
- WASTE STREAM TRACKING & REPORTING

